


BRUHATH BANGALORE MAHANAGARA PALIKE - DASARAHALLI ZONE

Office of the Executive Engineer, Dasarahalli Division

SCHEDULE - B

Name of Work: Construction of Culverts in 3rd main road at Ravindranagara, in Shettyhalli Sub Division, In Ward No-13. Under 22.75% Grants

Sl. No.	Description	Unit	Qty	Sanctioned Rates	
				In Figures	In words
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m after breaking of clods complete as per specifications. Specification No. KBS 2.1(a)/ 2 3.5	Cum	307.08	109.18	Rs. One Hundred and Nine & Eighteen Paise Only
2	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.2	Cum	26.57	3153.50	Rs. Three Thousand One Hundred and FiftyThree & Fifty Paise Only
3	Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.2	Cum	1.06	3845.68	Rs. Three Thousand Eight Hundred and FortyFive & SixtyEight Paise Only
4	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted, vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-15 (1:2:4) for raft foundation, column footing, main and secondary beams.	Cum	61.10	4386.23	Rs. Four Thousand Three Hundred and EightySix & TwentyEight Paise only
5	Providing and removing centering, shuttering, strutting, propping etc., for edges o slabs and breaks in floor, cills, plinth including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2	Sqm	445.68	478.14	Rs. Four Hundred and Seventy Eight & FortyFour Paise Only
6	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications	Sqm	113.40	1432.15	Rs. One Thousand Four Hundred and ThirtyTwo & Fifteen Paise Only



ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ


ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು



Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

1	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3	Q	42.77	5034.14	Rs. Five thousand ThirtyOne & Fourteen paise only
3	Conveying the excavated earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete.	Cum	261.00	71.34	Rs. Seventy One & ThirtyFour paise only


Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore


ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
Dasarahalli Zone
ಬೃಹತ್ ಮಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬಿ.ಬಿ.ಎಂ. ಬೆಂಗಳೂರು
ದಾಸರಹಳ್ಳಿ, ವಲಯ, ಬೆಂಗಳೂರು